

GOVERNMENT EMPLOYEES RETIREMENT SYSTEM HEAD QUARTERS BUILDING 48-50C KRONPRINDSENS GADE ST. THOMAS VIRGIN ISLANDS 00802 METAL ROOF REPAIR PROJECT

PREPARED BY



Jaredian Design Group

Architects, Engineers and Construction Managers

5333 RAADETS GADE, SUITE 14, ST. THOMAS, U. S. VIRGIN ISLANDS 00802-6900 • Post Office Box 6218, ST. THOMAS, U. S. VIRGIN ISLANDS 00804-6218
TELEPHONE: (340) 777.1600 • FAX: (340) 777.1601 • E-MAIL: jdg@vipowernet.net • WEBSITE: www.jaredian.com

SITE LOCATION PLAN




INDEX OF DRAWINGS

COVER SHEET

D1.0 DEMOLITION ROOF PLAN
A1.0 PROPOSED ROOF PLAN
A1.2 EXISTING ROOF
A1.4 DEMOLITION NOTES

S1.0 ROOF DETAILS
S1.1 ROOF DETAIL

ISLAND MAP



DATE: 6/10/2020

	1	2	3	4	5	6	7	
	GENERAL DEMOLITION NOTES				GENERAL NOTES			
E	1.	CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AND BE FAMILIAR WITH ALL SYSTEMS BEFORE DEMOLITION. ALL DEMOLITION SHALL COMPLY WITH THE RULES & REGULATIONS OF THE FEDERAL, STATE, COUNTRY AND CITY GOVERNMENTS. EXISTING SERVICES SHALL BE MAINTAINED DURING DEMOLITION. ANY SHUTDOWN OF SYSTEMS MUST BE COORDINATED & APPROVED BY THE OWNER. CONTRACTOR SHOULD COORDINATE WORK WITH ALL TRADES & PROVIDE SUPERVISION WHILE WORK IS BEING PERFORMED.				1.	ALL LUMBER USED SHALL BE PRESSURE TREATED	
	2.	THE CONTRACTOR SHALL VERIFY WITH THE OWNER, ALL MATERIALS TO BE RETAINED BY THE OWNER & DELIVER & STORE SAME WHERE DIRECTED BY THE OWNER. ALL REMAINING ITEMS BECOME THE PROPERTY OF THE CONTRACTOR & SHALL BE DISPOSED OF IN A LEGAL MANNER.				2.	ALL PLYWOOD JOINTS SHALL BE STAGGERED	
	3.	DO NOT INTERFERE WITH USE OF ADJACENT AREAS. MAINTAIN FREE & SAFE PASSAGE TO & FROM ADJACENT AREAS. PROVIDE, ERECT & MAINTAIN BARRICADES & LIGHTING AS REQUIRED BY APPLICABLE REGULATORY ADVISORY TO PROTECT OCCUPANTS OF THE BUILDING & WORKERS.				3.	THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY DISCREPANCIES OR ERRORS AND SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO THE CONSTRUCTION OF THE ROOFING SYSTEM.	
D	4.	REMOVE EXISTING ELEMENTS AS INDICATED BY LEGEND. SURFACES OF EXISTING AREAS WHICH HAVE BEEN ALTERED BY DEMOLITION NOT SPECIFICALLY CALLED FOR SHALL BE REPAIRED & FINISHED TO MATCH THE ADJACENT SURFACES. PROTECT ALL EXISTING OR REMAINING SURFACES, FLOORS, WALLS & CEILINGS FROM AREAS OF DEMOLITION & NEW CONSTRUCTION.				4.	CONTRACTOR TO REMOVE ALL TEMPORARY AND EXISTING ROOFING SYSTEMS.CONTRACTOR SHALL REMOVE ONLY AS MUCH EXISTING ROOFING SYSTEM THAT CAN BE RE-ROOFED IN ONE DAY. CONTRACTOR SHALL PROVIDE ALL NECESSARY TARPAULINS AND TEMPORARY MEASURE TO PROTECT THE ROOF FROM THE ELEMENTS.	E
	5.	CONTRACTOR SHALL FIELD VERIFY THE EXISTING CONDITIONS & NOTIFY THE ARCHITECT OF DISSIMILARITIES BEFORE PROCEEDING WITH DEMOLITION WORK. ALL WORK SHALL BE COORDINATED WITH DRAWINGS FOR NEW CONSTRUCTION.				5.	CONTRACTOR TO PROVIDE AND INSTALL ALL NECESSARY VENT, EXHAUST FANS ,FLASHING, COPING PITCH POCKETS WALK WAY PADS, HEAD WALL FLASHING EXPANSION JOINTS ETC. TO MAKE THE ROOFING SYSTEM COMPLETE. NEW CRICKETS TO BE FORMED WITH PREFBRICATED ROOF CURB ASSEMBLY SYSTEM.	
	6.	CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO DEMOLITION OR CONSTRUCTION IN EXISTING AREAS				6.	CONTRACTOR TO UTILIZE THE FOLLOWING CODE FOR DESIGN AND INSTALLATION OF THE ROOFING SYSTEM: INTERNATIONAL BUILDING CODE (LATEST ADDITION) FLORIDA-DADE COUNTY CODE FOR WIND RESISTANCE. CONTRACTOR MUST MEET OR EXCEED MENTIONED CODES.	D
C	7.	ARRANGE & PAY FOR DISCONNECTING, REMOVING & CAPPING UTILITY SERVICES WITHIN AREAS OF DEMOLITION. DISCONNECT & STUB-OFF, NOTIFY THE AFFECTED UTILITY COMPANY & OBTAIN APPROVAL BEFORE STARTING THIS WORK.				7.	CONTRACTOR TO VERIFY ALL EXISTING FIELD DIMENSIONS, EQUIPMENT LOCATION AND CONDITIONS AND NOTIFY THE ARCHITECT/ENGINEER OF ANY DISCREPANCIES.	
	8.	REMOVE FROM THE SITE ALL CONTAMINATED, VERMIN INFESTED OR DANGEROUS MATERIALS ENCOUNTERED & DISPOSE OF BY LEGAL MEANS. DO NOT ENDANGER THE HEALTH OF WORKERS OF THE PUBLIC.				8.	THE DRAWINGS DO NOT INDICATE ALL OF THE ITEMS ON THE ROOF OR PENETRATIONS IN THE ROOF. CONTRACTOR IS REQUIRED TO SURVEY THE ROOF AND REPLACE ALL FLASHING WHERE REQUIRED WITH ROOFING WORK.REPLACE ALL CAP FLASHING AROUND ALL MISCELLANEOUS FANS,VENTS,SKYLIGHTS,ETC. HIP FLASHING WILL NOT BE REPLACED.	C
	9.	THE OWNER RESERVES THE RIGHT TO SALVAGE ANY MATERIAL OR PORTION THEREOF FROM DEMOLISHED MATERIAL BEFORE IT IS DISPOSED OF.				9.	EXISTING METAL PURLINS TO REMAIN.	
B	10.	CONTRACTOR TO REMOVE EXISTING METAL ROOFING SYSTEM AND FRAMING ON BUILDING ROOFS TO BE REPLACED.				10.	LIFTING OF EXISTING HVAC UNITS (WHERE PRACTICAL), EXHAUST FANS, PIPING AND RELATED ROOF ACCESSORIES TO ACCOMMODATE ROOFING OPERATIONS THEN RESETTNG UNITS ON NEW CURBS AND SUPPORTS,(WHERE PRACTICAL AND PLACED IN OPERATING CONDITION UPON COMPLETION. COORDINATE WITH GERS FOR SHUT-DOWNS. AND/OR DISCONNECTS.	B
	11.	REMOVE EXISTING METAL ROOFING SYSTEMS,INCLUDING WOOD FRAMING ON BUILDINGS INDICATED FOR ROOF REPAIRS.				11.	REMOVAL OF LIGHTNING PROTECTION SYSTEM / ANTENNAS AND COMPONENTS AND SUBSEQUENT REPLACEMENT AND RE-CERTIFICATION OF SAME UPON COMPLETION.THE REPLACEMENT OF THE LIGHTNING / ANTENNAS PROTECTION WIRE SHOULD MATCH THE TYPE AND SIZE OF THE EXISTING.	
						12.	CONTRACTOR TO INSTALL INTERMEDIATE PURLINS AT 2'-0" O.C. MAXIMUM.	
						13.	CONTRACTOR SHALL REMOVE EXISTING INSULATION AND REPLACE WITH NEW INSULATION.	
A								A
	1	2	3	4	5	6	7	

5

6

7

GENERAL NOTES

1. ALL LUMBER USED SHALL BE PRESSURE TREATED
2. ALL PLYWOOD JOINTS SHALL BE STAGGERED
3. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY DISCREPANCIES OR ERRORS AND SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO THE CONSTRUCTION OF THE ROOFING SYSTEM.
4. CONTRACTOR TO REMOVE ALL TEMPORARY AND EXISTING ROOFING SYSTEMS. CONTRACTOR SHALL REMOVE ONLY AS MUCH EXISTING ROOFING SYSTEM THAT CAN BE RE-ROOFED IN ONE DAY. CONTRACTOR SHALL PROVIDE ALL NECESSARY TARPULINS AND TEMPORARY MEASURE TO PROTECT THE ROOF FROM THE ELEMENTS.
5. CONTRACTOR TO PROVIDE AND INSTALL ALL NECESSARY VENT, EXHAUST FANS, FLASHING, COPING PITCH POCKETS WALK WAY PADS, HEAD WALL FLASHING EXPANSION JOINTS ETC. TO MAKE THE ROOFING SYSTEM COMPLETE. NEW CRICKETS TO BE FORMED WITH PREFABRICATED ROOF CURB ASSEMBLY SYSTEM.
6. CONTRACTOR TO UTILIZE THE FOLLOWING CODE FOR DESIGN AND INSTALLATION OF THE ROOFING SYSTEM:
INTERNATIONAL BUILDING CODE
(LATEST ADDITION)
FLORIDA-DADE COUNTY CODE
FOR WIND RESISTANCE.
CONTRACTOR MUST MEET OR EXCEED
MENTIONED CODES.
7. CONTRACTOR TO VERIFY ALL EXISTING FIELD DIMENSIONS, EQUIPMENT LOCATION AND CONDITIONS AND NOTIFY THE ARCHITECT/ENGINEER OF ANY DISCREPANCIES.
8. THE DRAWINGS DO NOT INDICATE ALL OF THE ITEMS ON THE ROOF OR PENETRATIONS IN THE ROOF. CONTRACTOR IS REQUIRED TO SURVEY THE ROOF AND REPLACE ALL FLASHING WHERE REQUIRED WITH ROOFING WORK. REPLACE ALL CAP FLASHING AROUND ALL MISCELLANEOUS FANS, VENTS, SKYLIGHTS, ETC. HIP FLASHING WILL NOT BE REPLACED.
9. EXISTING METAL PURLINS TO REMAIN.
10. LIFTING OF EXISTING HVAC UNITS (WHERE PRACTICAL), EXHAUST FANS, PIPING AND RELATED ROOF ACCESSORIES TO ACCOMMODATE ROOFING OPERATIONS THEN RESETTING UNITS ON NEW CURBS AND SUPPORTS, (WHERE PRACTICAL AND PLACED IN OPERATING CONDITION UPON COMPLETION. COORDINATE WITH GERS FOR SHUT-DOWNS. AND/OR DISCONNECTS.
11. REMOVAL OF LIGHTNING PROTECTION SYSTEM / ANTENNAS AND COMPONENTS AND SUBSEQUENT REPLACEMENT AND RE-CERTIFICATION OF SAME UPON COMPLETION. THE REPLACEMENT OF THE LIGHTNING / ANTENNAS PROTECTION WIRE SHOULD MATCH THE TYPE AND SIZE OF THE EXISTING.
12. CONTRACTOR TO INSTALL INTERMEDIATE PURLINS AT 2'-0" O.C. MAXIMUM.
13. CONTRACTOR SHALL REMOVE EXISTING INSULATION AND REPLACE WITH NEW INSULATION.

A



UNIVERSITY OF THE VIRGIN ISLANDS

